

[Link to 2024 IBC](#)
 [Link to 2021 IBC](#)
 [Link to 2018 IBC](#)
 [Link to 2020 MN Building Code](#)
 [Link to MN Rules 1305 Amendments](#)
[Link to 2024 IEBC \(Conservation Code\)](#)
 [Link to 2021 IEBC](#)
 [Link to 2020 MN Conservation Code](#)

To Be Completed by TAG Leads											TAG Meeting Results					
Item Number	2024 Code and Chapter		2024 Code & Section	2021 Code & Section	2020 MN Code Section	Code Section Heading/Topic	MN Amendment?	Description of change(s) to code language	Safety/Health Value	Cost Impact	Staff Comment	Staff Recommendation	TAG Recommendation	TAG Group Consensus	Stakeholder Consensus	Comments
	Code	Chapter												Y or N	Y or N	
IBC/MR 1305 Chapter 16 - Structural Design																
13-B16	IBC	16	1602.1	1602.1	1602.1	Notations		Changes in 2021 and 2024 E, L, Pg(asd), Pg, V, V _T .	L	L						Table 5/2. Discussed 5/16- Tabled.
16-B16	IBC	16	Table 1604.3	Table 1604.3	Table 1604.3	Deflection Limits		2024, added footnote j, snow load can be taken at .7 design snow for deflection limits.	M	L						Table 5/2. Discussed 5/16- Tabled.
72-B16	IBC	16	1608.2; Figures 1608.2(1) - 1608.2(4)		1608.2; MR 1305.1608.2	Ground Snow Loads	Y	Subsection revised 2024. Figures revised. MN amendment does not reference Figures. Changing reference for loading to ASCE 7 Hazard Tool https://asce7hazardtool.online/ .	H		Coordinate with 1303 and 1309.					Table 5/2. Discussed 5/16- Tabled.
177-B19	IBC	19			1305.1904.3	Corrosion Protection	Y	Amendment adds subsection. 1904.3 Corrosion protection. Where bonded reinforcing and prestressing steel is located in concrete assigned to Exposure Class F3 or Exposure Class C2, the steel shall be protected from corrosion by one of the following methods: 1. Impermeable barrier. 2. Epoxy coating in accordance with ACI 318. 3. Hot dipped galvanizing in accordance with ACI 318.								Tabled 6/6/24 MO to research ACI 318-19.
IBC/MR 1305 Chapter 24 - Glass and Glazing																
236-B24	IBC	24	Throughout Chapter		Throughout Chapter	Basic Wind Speed References		In 2024, throughtout Chapter 24, "basic design wind speed" changed to "basic wind speed".					A	Y		TAG accepts all instances.
237-B24	IBC	24	2407.1.1		2407.1.1			2407.1.1 Loads. Glass handrails and guards and their support systems shall be designed to withstand the loads specified in Section 1607.9. Glass handrails and guards shall be designed using a factor of safety of four. Calculated stresses for the loads specified in Section 1607.9 shall be less than or equal to 3,000 pounds per square inch (20.7 MPa) for heatstrengthened glass and less than or equal to 6,000 pounds per square inch (41.4 MPa) for fully tempered glass.								

[Link to 2024 IBC](#)
 [Link to 2021 IBC](#)
 [Link to 2018 IBC](#)
 [Link to 2020 MN Building Code](#)
 [Link to MN Rules 1305 Amendments](#)
[Link to 2024 IEBC \(Conservation Code\)](#)
 [Link to 2021 IEBC](#)
 [Link to 2020 MN Conservation Code](#)

To Be Completed by TAG Leads													TAG Meeting Results				
Item Number	2024 Code and Chapter		2024 Code & Section	2021 Code & Section	2020 MN Code Section	Code Section Heading/Topic	MN Amendment?	Description of change(s) to code language	Safety/Health Value	Cost	Impact	Staff Comment	Staff Recommendation	TAG Recommendation	TAG Group Consensus	Stakeholder Consensus	Comments
	Code	Chapter													Y or N	Y or N	
238-B24	IBC	24	2409.1		2409.1	Glass Walkways		Reorganized to create items 1 and 2. 2409.1 Glass walkways. Glass installed as a part of a floor/ceiling assembly as a walking surface and constructed with laminated glass shall comply with either of the following: 1. ASTM E2751. 2. Load requirements specified in Chapter 16 and approval in accordance with the provisions of Section 104.2.3. Such assemblies shall comply with the fire-resistance rating and marking requirements of this code where applicable.									
IBC/MR 1305 Chapter 30 - Elevators and Conveying Systems																	
239-B30	IBC	30	3001.6			Structural Design		New section 2024. 3001.6 Structural design. All interior and exterior elevators, escalators and other conveying systems and their components shall comply with all applicable design loading criteria in Chapter 16, including wind, flood and seismic loads established in Sections 1609, 1612 and 1613.									
IBC/MR 1305 Chapter 31 - Special Construction																	
240-B31	IBC	31	3103.1.1			Temporary Structures, Extended Period of Service Time		New in 2024. Provides requirements for extensions of service time, including analysis by design pro for adequacy to resist 3103.6 structural loads.									
241-B31	IBC	31	3103.6; 3103.6.1; 3103.6.1.1; T3106.1.1; 3103.6.1.2; T3103.6.1.2; 3103.3.6.1.3; 3103.6.1.4; 3103.6.1.5; 3103.6.1.6			Temporary Structures, Structural Requirements		New in 2024. Section addresses structural requirements for temporary structures, risk categories, structural loads including snow, wind, flood, seismic, ice and tsunami loads.									

[Link to 2024 IBC](#)
 [Link to 2021 IBC](#)
 [Link to 2018 IBC](#)
 [Link to 2020 MN Building Code](#)
 [Link to MN Rules 1305 Amendments](#)
[Link to 2024 IEBC \(Conservation Code\)](#)
 [Link to 2021 IEBC](#)
 [Link to 2020 MN Conservation Code](#)

To Be Completed by TAG Leads **TAG Meeting Results**

To Be Completed by TAG Leads														TAG Meeting Results			
Item Number	2024 Code and Chapter		2024 Code & Section	2021 Code & Section	2020 MN Code Section	Code Section Heading/Topic	MN Amendment?	Description of change(s) to code language	Safety/Health Value	Cost	Impact	Staff Comment	Staff Recommendation	TAG Recommendation	Recommendations A - Accept Model Code AM - Amend Model Code		Comments
	Code	Chapter													TAG Group Consensus	Stakeholder Consensus	
	Y or N	Y or N															
242-B31	IBC	31	3103.6.2			Temporary Structures, Foundations		New in 2024. <i>Foundations. Public-occupancy temporary structures shall be permitted to be supported on the ground with temporary foundations where approved by the building official. Consideration shall be given for the impacts of differential settlement where foundations do not extend below the ground or where foundations are supported on compressible materials. The presumptive load-bearing value for public-occupancy temporary structures supported on a pavement, slab on grade or on other collapsible or controlled low-strength substrate soils such as beach sand or grass shall be assumed not to exceed 1,000 pounds per square foot (47.88 kPa) unless determined through testing and evaluation by a registered design professional. The presumptive load-bearing values listed in Table 1806.2 shall be permitted to be used for other supporting soil conditions.</i>									
243-B31	IBC	31	Section 3114		Section 3115	Intermodal Shipping Containers		Entire section new in 2021, renumbered in 2024. Note a Code Change Proposal via 1305/IBC TAG related to ISCs has no structural changes proposed.									
IBC/MR 1305 Chapter 33 - Safeguards During Construction																	

[Link to 2024 IBC](#)
 [Link to 2021 IBC](#)
 [Link to 2018 IBC](#)
 [Link to 2020 MN Building Code](#)
 [Link to MN Rules 1305 Amendments](#)
[Link to 2024 IEBC \(Conservation Code\)](#)
 [Link to 2021 IEBC](#)
 [Link to 2020 MN Conservation Code](#)

To Be Completed by TAG Leads **TAG Meeting Results**

Recommendations A - Accept Model Code AM - Amend Model Code

Item Number	2024 Code and Chapter		2024 Code & Section	2021 Code & Section	2020 MN Code Section	Code Section Heading/Topic	MN Amendment?	Description of change(s) to code language	Safety/Health Value	Cost	Impact	Staff Comment	Staff Recommendation	TAG Recommendation	TAG Group Consensus	Stakeholder Consensus	Comments
	Code	Chapter													Y or N	Y or N	
244-B33	IBC	33	3307.2; 3307.2.1; 3307.2.2; 3307.2.3			Protection of Adjoining Property, Excavation Retention Systems		New section in 2021. 3307.2 Excavation retention systems. Where a retention system is used to provide support of an excavation for protection of adjacent property or structures , the system shall conform to the requirements in Sections 3307.2.1 through 3307.2.3. <i>[BS] 3307.2.1 Excavation retention system design. Excavation retention systems shall be designed by a registered design professional to provide vertical and lateral support.</i> <i>[BS] 3307.2.2 Excavation retention system monitoring. The retention system design shall include requirements for monitoring of the system and adjacent property or structures for horizontal and vertical movement.</i> <i>[BS] 3307.2.3 Retention system removal. Elements of the system shall only be removed or decommissioned where adequate replacement support is provided by backfill or by the new structure . Removal or decommissioning shall be performed in such a manner that protects the adjacent property.</i>									
MR 1303 Chapter 33 - Minnesota Provisions																	
245-MP					MR 1303.1600	Footing Depth for Frost Protection		Administration and Minnesota Provisions TAG members and Structural TAG members jointly discuss a code change proposal to revise frost depth requirements									